


LEGEND

Existing Tree to be Retained	Existing Tree to be Removed	Existing Tree in poor condition to be Removed	Existing Dead Tree to be Removed	Existing Tree to be Transplanted	Undersize tree, existing dead tree, or Stump	Tree Protection Fencing


Tree Tag Legend
 XX - Tag number
 C-XX - Municipal tree
 OS-XX - Off-site tree
 S-XX - Straddling tree. Written permission required from owner to remove trees.
 XX(HP) - Hand-plotted
 XX-NT - No Tag #



Note:

1. Contact VDZ+A Project Arborist (Glyn Romaine (glyn@vdz.ca)) for inspection 72 hrs prior to any grading or excavation within the tree protection zone. (typ) If during excavation it is found that it cannot be completed without severing roots that are critical to the trees health or stability it may be necessary to remove additional trees.
2. Read this plan together with the arborist report prepared by VDZ+A.
3. An additional 1m setback is shown for all hand-plotted trees to be retained
4. If Stump Grinding is to occur in close proximity to trees which are to be retained then it is requested stumps to be removed under Arborist supervision.
5. It is the responsibility of the client or his/her representative to contact the project arborist for the purpose of:
 *Locating TPZ Fencing
 *Locating Work Zone and Machine access corridors where required
 *Reviewing the Report with the project foreman or site supervisor.

SCHEDULE C
Specification for Tree Protection Barriers



Notes:

1. A protective barrier must be installed around every tree to be retained prior to the work commencing onsite, and that barrier must remain intact until the Director has authorized its removal.
2. Any excavation adjacent to the protective barrier must be done by hand.
3. Maintenance of trees that are to remain must include watering and application of 10 cm of mulch, but will not include any cutting or pruning of branches or roots unless approved by the Director in advance.
4. The dimensions of the protective barrier must be equal to the extent of the drip line, or six times the tree diameter, whichever is greater.
5. Measurements in relation to tree diameter must be taken at 1.4 m above the soil surface.



5			
4			
3			
2	GYL	Issued for AR Update	2025-11-05
1	GYL	Issued for Arborist Report	2025-10-06
REV	BY	DESCRIPTION	DATE
REVISIONS TABLE FOR DRAWINGS			
© Copyright reserved. This drawing is the property of VDZ+A and may not be reproduced or used for other projects without permission.			
REV	BY	DESCRIPTION	DATE
REVISIONS TABLE FOR SHEET			

Project:
Cascades Delta Hotel Expansion

Location:
6005 Hwy 17A @ Hwy 99
Delta, B.C.

Drawn: GYL	Stamp:
Checked: DGR	
Approved:	Original Sheet Size: 24"x36"
	Scale: 1:500

VDZ+A and its staff are not responsible for any errors or omissions in this drawing or any other drawings. All drawings are the property of VDZ+A and may not be reproduced or used for other projects without permission.